



Addendum No. 1

City of Coquitlam
Tender 72487

**2024 Pavement Rehabilitation - David Avenue &
Local Roads (Fleming, Hoy, Reece and Bouthot)**
(Consists of 4 Pages)

Issue Date: March 6, 2024

Tenderers shall note the following changes:

REVISIONS:

1. REFER to: FORM OF TENDER

REMOVE: Appendix 1

REPLACE WITH: **REVISED** – Appendix 1 – **REVISION NO. 1**

CONTRACTOR QUESTIONS and CLARIFICATIONS:

Q1) How is the asphalt curb on the Local roads portion of the contract to be paid?

A1) Refer to Supplementary Contract Specifications; Section 32 12 16S. Payment for asphalt curb shown on drawings will be considered as incidental to the cost of asphalt concrete paving.

Q2) As item 10.01 for the local roads package is a 75mm single lift asphalt structure, please confirm if item 9.01 asphalt tack coat is required for this portion of the contract.

A2) Please refer to **REVISED – Appendix 1 – **REVISION NO. 1****

Q3) For the local roads package, from the SOQ item 6.01 Description states "Full depth milling (all depths), minimum 125mm". This is in conflict with the drawings which state a minimum of 100mm. Please confirm which is correct.

A3) Please refer to **REVISED – Appendix 1 – **REVISION NO. 1****

Q4) For the local roads package, SOQ item 8.01 19mm minus granular base, please confirm the quantity for this item as the SOQ quantity seems excessively high for the 25mm depth required on the drawings.

A4) Please refer to **REVISED – Appendix 1 – **REVISION NO. 1****

End of Addendum No. 1

Tenderers shall take into account the content of this Addendum in the preparation and submission of the Tender which will form part of the contract and should be acknowledged on the Tender form where indicated.

Upon submitting a Tender, Tenderers will be deemed to have received all addenda and considered the information for inclusion in the Tender submitted.

Issued by:

M. Pain
Purchasing Manager
Email: bid@coquitlam.ca

Revised - APPENDIX 1 - Revision No. 1**FORM OF TENDER****Contract 72487****2024 Pavement Rehabilitation - David Avenue & Local Roads (Fleming, Hoy, Reece and Bouthot)****SCHEDULE OF QUANTITIES AND PRICES**

(see paragraph 5.3.1 of the Instruction to Tenderers)

(All prices and quotations including the Contract Prices shall Exclude GST)

(Should there be any discrepancy in the information provided, the City's original file copy shall prevail)

PAVEMENT REHABILITATION - DAVID AVENUE (GLENBROOK STREET TO COAST MERIDIAN ROAD)						
ITEM NO.	MMCD Ref./ (SS)	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	EXTENDED AMOUNT
1.00	01 55 005	TRAFFIC CONTROL, VEHICLE ACCESS AND PARKING				
1.01	(1.5.1)	Traffic Control and Management		Incidental to Contract		
2.00	01 57 015	ENVIRONMENTAL PROTECTION				
2.01	(1.6.1)	ESC supply & installation, maintenance and removal		Incidental to Contract		
3.00	01 58 015	PROJECT IDENTIFICATION				
3.01	(1.3.1)	Construction Zone Information Signs	ea.	5		
3.02	(1.3.2)	Changeable Message Moard Signs (x2)	week	3		
4.00	26 56 015	ROADWAY LIGHTING				
4.01	1.9.1	Supply & installation of Roadway and Pedestrian Lighting (ALL) Works including any removal, adjustments and disposal needed to complete the work and as shown on the Contract Drawing	ea.	1		
5.00	31 22 165	RESHAPING GRANULAR ROADBEDS				
5.01	(1.4.1)	Reshaping	sq.m	5,810		
6.00	31 24 135	ROADWAY EXCAVATION, EMBANKMENT AND COMPACTION				
6.01	(1.8.10)	Over Excavation (including offsite Disposal) - (Provisional)	cu.m	30		
7.00	32 01 16.75	COLD MILLING				
7.01	(1.5.4)	Full Depth Milling (all depths), minimum 150mm	sq.m	5,810		
8.00	32 11 16.15	GRANULAR SUBBASE				
8.01	(1.4.3)	75mm Minus Granular Subbase (Variable Thickness) - (Provisional)	tonne	20		
9.00	32 11 235	GRANULAR BASE				
9.01	(1.4.3)	25mm Minus Granular Base (Variable Thickness) - (Provisional)	tonne	340		
10.00	32 12 13.15	ASPHALT TACK COAT				
10.01	(1.5.1)	Asphalt Tack Coat - Emulsified Asphalt	sq.m	5,810		
11.00	32 12 165	HOT-MIX ASPHALT CONCRETE PAVING				
11.01	(1.5.1)	Asphaltic Concrete Paving - 19mm MOTI Class 1 Medium Mix (80-100) Group Asphalt (50mm)	tonne	820		
11.02	(1.5.1)	Asphaltic Concrete Paving - MMCD Lower Course #1 (75mm)	tonne	1,230		
12.00	32 17 235	PAINTED PAVEMENT MARKINGS				
12.01	(1.5.3)	Line Painting & Permanent Thermoplastic Pavement Markings Including Green MMA Paint	l.s.	1		
12.02	(1.5.4.3)	Remove Existing Signs	l.s.	1		
13.00	33 44 015	MANHOLES AND CATCHBASINS				
13.01	(1.5.3.1)	Manhole Frame and Lid Replacement and Adjustment as Directed by CA (Provisional)	ea.	6		
13.02	(1.5.3.1)	Manhole Frame and Cover Adjustment Only as Directed by CA (Provisional)	ea.	4		
13.03	(1.5.3.2)	Water Valve Box Replacement - Terminal City Nelson Type as Directed by CA (Provisional)	ea.	10		
13.04	(1.5.3.3)	Catch Basin Replacement - Top Inlet Type as per MMCD S11 as Directed by CA (Provisional)	ea.	2		
Sub-Total for David Avenue:						

PAVEMENT REHABILITATION - LOCAL ROADS (REECE AVENUE, IRVINE STREET, FLEMING AVENUE, BOUTHOT STREET)						
ITEM NO.	MMCD Ref./ (SS)	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	EXTENDED AMOUNT
1.00	01 55 005	TRAFFIC CONTROL, VEHICLE ACCESS AND PARKING				
1.01	(1.5.1)	Traffic Control and Management		Incidental to Contract		
2.00	01 57 015	ENVIRONMENTAL PROTECTION				

ITEM NO.	MMCD Ref./(SS)	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	EXTENDED AMOUNT
2.01	(1.6.1)	ESC supply & installation, maintenance and removal		Incidental to Contract		
3.00	01 58 015	PROJECT IDENTIFICATION				
3.01	(1.3.1)	Construction Zone Information Signs	ea.	3		
4.00	31 22 165	RESHAPING GRANULAR ROADBEDS				
4.01	(1.4.1)	Reshaping	sq.m	6,565		
4.02	(1.4.1)	Shoulder Grading (Provisional)	sq.m	135		
5.00	31 24 135	ROADWAY EXCAVATION, EMBANKMENT AND COMPACTION				
5.01	(1.8.5)	Common Excavation (including offsite Disposal)	cu.m	30		
5.02	(1.8.10)	Over Excavation (including offsite Disposal) - (Provisional)	cu.m	67		
6.00	32 01 16.75	COLD MILLING				
6.01	(1.5.4)	Full Depth Milling (all depths), minimum 100mm	sq.m	6,565		
7.00	32 11 16.15	GRANULAR SUBBASE				
7.01	(1.4.3)	75mm Minus Granular Subbase (Variable Thickness) - (Provisional)	tonne	40		
8.00	32 11 235	GRANULAR BASE				
8.01	(1.4.3)	19mm Minus Granular Base (Variable Thickness)	tonne	380		
8.02	(1.4.3)	Shoulder Gravel (19mm Minus Granular Base) - 200mm Thick (Provisional)	tonne	70		
9.00	32 12 165	HOT-MIX ASPHALT CONCRETE PAVING				
9.01	(1.5.1)	Asphaltic Concrete Paving - MMCD Upper Course #1 (75mm)	tonne	1,385		
10.00	32 17 235	PAINTED PAVEMENT MARKINGS				
10.01	(1.5.3)	Line Painting & Permanent Thermoplastic Pavement Markings	l.s.	1		
11.00	33 44 015	MANHOLES AND CATCHBASINS				
11.01	(1.5.3.1)	Manhole Frame and Lid Replacement and Adjustment as Directed by CA (Provisional)	ea.	12		
11.02	(1.5.3.1)	Manhole Frame and Cover Adjustment Only as Directed by CA (Provisional)	ea.	5		
11.03	(1.5.3.2)	Water Valve Box Replacement - Terminal City Nelson Type as Directed by CA (Provisional)	ea.	5		
11.04	(1.5.3.3)	Catch Basin Replacement - Top Inlet Type as per MMCD S11 as Directed by CA (Provisional)	ea.	4		
11.05	(1.5.4.1)	Catch Basin Repairs - as Directed by CA (Provisional)	ea.	4		
Sub-Total for Local Roads:						

Total Tendered Price (exclude GST): _____

(Transfer the amount to Form of Tender Summary Page 1)

Name of Contractor: _____