



## Addendum No. 1

City of Coquitlam  
Tender 81294

### Harbour Drive Retaining Wall replacement

Issue Date: June 11, 2024  
(Consists of 2 Pages)

Tenderers shall note the following amendments to the **CONTRACT DOCUMENT** as follows:

#### Questions & Clarifications

- Q1) In the Schedule of Quantities and Prices, Pay Item 7.04 allowed for 18 L.M. of 1.8m tall fence including gates. This quantity does not seem to have the two gates included which is another 4 L.M. Please clarify.
- A1) The quantity for Pay Item 7.04 includes the two gates. Exact measurement for payment can be confirmed during construction as limits may change.**
- Q2) In the Schedule of Quantities and Prices, Pay Item 5.01, only 8 cu.m. of rock removal is accounted for. Does this pay item include removal of the rocks and concrete for the top wall and bottom wall?
- A2) Removal of the existing retaining walls (top and bottom) is included in the payment for Pay Item 6.01. Refer to Supplementary Contract Specifications Section 31 32 192 – Geosynthetics.**
- Refer to MMCD Supplementary Specifications Section 31 23 17 – Rock Removal, for definitions related to Pay Item 5.01.**
- Q3) To remove and dispose of concrete stairs and concrete spillway, we don't know which bid items these belong to. Please clarify and provide quantity.
- A3) Refer to Supplementary Contract Specifications Section 31 32 192 – Geosynthetics, Measurement and Payment clause. Removal and offsite disposal of concrete outfall structures and retaining walls (which include stairs and landing) are included as part of this pay item. This Pay Item is paid per a lump sum basis.**
- Q4) Is the concrete wall adjacent to the stairs to be removed and disposed? Can I consider the above lower wall and under the foot of stairs, the entire area is 6" thick cast concrete surface is to be removed and disposed?

- A4) Refer to above responses and refer to the Contract Drawings that show which structures are to be removed and which are to be retained.**
- Q5) The TetraTech drawings and notes do not specify a specific model number for the Terrafix TBX geogrid wrap like they do for the erosion control blanket or the geogrid reinforcement.
- A5) Refer to TetraTech Drawing Notes "3. MATERIALS". Material can be used as listed in this Notes section or alternative equivalent provided by the geogrid manufacturer and as approved by the Geotechnical Engineer through submission and review of shop drawings.**
- 

***End of Addendum No. 1***

Tenderers shall take into account the content of this Addendum in the preparation and submission of the Tender which will form part of the contract and should be acknowledged on the Tender form where indicated.

Upon submitting a Tender, Tenderers will be deemed to have received all addenda and considered the information for inclusion in the Tender submitted.

*Issued by:*

M. Pain  
Procurement Manager  
Email: [bid@coquitlam.ca](mailto:bid@coquitlam.ca)