



## **Addendum No. 1**

City of Coquitlam  
Tender No. 73580-1

### **Hillside Area West – LRN Pavement Rehab**

**Issue Date:** March 2, 2021

(Consists of 4 Pages including FT.5-Rev 1 & FT.6-Rev 1)

***Tenderers shall note the following amendments to the Tender documents:***

#### **1. Revisions - Schedule of Quantities and Prices:**

- R1)** Under the description for Pay Item 8.01 – “75mm Crushed Minus Granular Sub Base”, delete the qualifier “**(Provisional)**”.
- R2)** Under the description for Pay Item 9.01 – “19mm Crushed Minus Granular Base”, delete the qualifier “**(Provisional)**”.
- R3)** Under the description for Pay Item 11.01 – “Asphaltic Concrete Paving – (MMCD UC#1)”, remove the qualifier “**75mm thickness**” and replace with “**variable thickness**”

**REMOVE:**

Form of Tender Pages FT.5 & FT.6

**REPLACE WITH:**

Form of Tender Pages FT.5-Rev 1 & FT.6-Rev 1

#### **2. Questions and Clarification:**

- Q1) Please confirm no catch basins are to be removed on this project?
- A1) That is correct, no catch basins are to be removed. There are four lawn basins to be removed and relocated (See Drawing Sheet 36 & 37).**
- Q2) Tender drawings indicate 40mm mill and overlay sections, but there is not a 40mm surface paving pay item on the SOQ. Please advise?
- A2) Quantities for the 40mm surfaced lift are combined into Pay Item 11.01 –Asphaltic Concrete Paving (MMCD UC#1). Description has been changed to indicate variable thickness.**

- Q3) Various thicknesses of asphalt driveway are noted on the tender drawings. Will they all be paid under Item 11.02?
- A3) All asphalt driveway will be paid under Pay Item 11.02 – Asphaltic Concrete Driveway (MMCD UC#2) at the 60mm thickness. There are two Lane entrances incorrectly marked as driveways and shown as 75mm thick. These will be paid under Pay Item 11.01 – Asphaltic Concrete Paving (MMCD UC#1).**
- 

***End of Addendum No. 1***

**Tenderers shall take into account the content of this Addendum in the preparation and submission of the Tender which will form part of the contract and should be acknowledged on the Tender Form, Item 1.**

Upon submitting a Tender, Tenderers will be deemed to have received all Addenda that are posted on the City's website and deemed to have considered the information for inclusion in the Tender submitted.

*Issued by:*

M. Pain  
Purchasing Manager  
[bid@coquitlam.ca](mailto:bid@coquitlam.ca)

**REVISED - Appendix 1 - Revision No. 1  
FORM OF TENDER**

**Contract 73580-1  
Hillside Area West - LRN Pavement Rehab**

**SCHEDULE OF QUANTITIES AND PRICES**

(see paragraph 5.3.1 of the Instruction to Tenderers)  
(All prices and quotations including the Contract Prices shall Exclude GST)  
(Should there be any discrepancy in the information provided, the City's original file copy shall prevail)

ITEM NO.	MMCD Ref./ (SS)	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	EXTENDED AMOUNT
<b>1.00</b>	<b>DIV 01</b>	<b>GENERAL REQUIREMENTS</b>				
1.01	01 45 00 (1.7)	Quality Control Testing			INCIDENTAL	
1.02	01 55 00 (1.5.1)	Traffic Control and Management			INCIDENTAL	
1.03	01 57 01 (1.6.1)	Environmental Protection			INCIDENTAL	
<b>2.00</b>	<b>01 58 01</b>	<b>PROJECT IDENTIFICATION</b>				
2.01	(1.3.1)	1.2m x 1.2m Static Construction Zone Information Sign	EACH	8		\$0.00
<b>3.00</b>	<b>03 30 20</b>	<b>CONCRETE WALKS, CURBS, &amp; GUTTERS</b>				
3.01	(1.4.3)	Concrete Rollover Curb and Gutter - MMCD C4 (excl. gravels)	L.M.	5		\$0.00
3.02	(1.4.3)	Concrete Barrier Curb and Gutter - MMCD C5 (excl. gravels)	L.M.	55		\$0.00
3.03	(1.4.3)	Concrete Extruded Curb - COQ-C6 (excl. gravels)	L.M.	30		\$0.00
3.04	(1.4.5)	Concrete Sidewalk (MMCD -C2) - Broom Finish -100mm thick - (excl. gravels)	SQ. M	390		\$0.00
3.05	(1.4.5)	Concrete Driveway Letdown (COQ-C7)- 190mm thick - (excl. gravels)	SQ. M	380		\$0.00
3.06	(1.4.5)	Concrete Driveway -Broom Finish-150mm thick -(excl. gravels)	SQ. M	120		\$0.00
<b>4.00</b>	<b>31 22 16</b>	<b>RESHAPING GRANULAR ROADBED</b>				
4.01	(1.4.1)	Reshaping Road Bed	SQ. M	25790		\$0.00
4.02	(1.4.1)	Shoulder Grading (back of drain curb, etc)	SQ. M	90		\$0.00
<b>5.00</b>	<b>31 11 01</b>	<b>CLEARING AND GRUBBING</b>				
5.01	(1.4.1)	Remove/Trim Existing Vegetation (Trees, Hedges, Shrubs, etc)	L.S.	1		\$0.00
<b>6.00</b>	<b>31 24 13</b>	<b>ROADWAY EXCAVATION, EMBANKMENT, &amp; COMPACTION</b>				
6.01	(1.8.5)	Common Excavation	C.M.	290		\$0.00
6.02	(1.8.10)	Over Excavation (including Disposal, Backfill, & Compaction) - (Provisional)	C.M.	900		\$0.00
6.03	(1.8.4)	Removal of Existing Asphalt Curb	L.M.	100		\$0.00
6.04	(1.8.4)	Removal of Existing Concrete Curb	L.M.	60		\$0.00
6.05	(1.8.4)	Removal of Existing Asphalt Flatwork (Incl. Sawcut & Offsite Disposal)	SQ. M	540		\$0.00
6.06	(1.8.4)	Removal of Existing Concrete Flatwork (Incl. Sawcut & Offsite Disposal)	SQ. M	250		\$0.00
<b>7.00</b>	<b>32 01 16.7</b>	<b>COLD MILLING</b>				
7.01	(1.5.4)	Surface Milling (up to 40mm)	SQ. M	2310		\$0.00
7.02	(1.5.4)	Full Depth Milling including Granular Material (up to 125mm)	SQ. M	25790		\$0.00
<b>8.00</b>	<b>32 11 16.1</b>	<b>GRANULAR SUBBASE</b>				
8.01	(1.4.1/3)	75mm Crushed Minus Granular Sub Base	Tonne	20		\$0.00

ITEM NO.	MMCD Ref./ (55)	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	EXTENDED AMOUNT
<b>9.00</b>	<b>32 11 23</b>	<b>GRANULAR BASE</b>				
9.01	(1.4.1)	19mm Crushed Minus Granular Base	Tonne	3420		\$0.00
<b>10.00</b>	<b>32 12 13.1</b>	<b>ASPHALT TACK COAT</b>				
10.01	1.5.1	Asphalt Tack Coat - Emulsified Asphalt	SQ. M	2310		\$0.00
<b>11.00</b>	<b>32 12 16</b>	<b>HOT-MIX ASPHALT CONCRETE PAVING</b>				
11.01	(1.5.1)	Asphaltic Concrete Paving - (MMCD UC#1)- variable thickness	Tonne	5230		\$0.00
11.02	(1.5.3)	Asphaltic Concrete Driveway - (MMCD UC#2) 60mm thickness	Tonne	93		\$0.00
11.03	(1.5.4)	Asphalt Drainage Curb (50mm/25mm height)	L.M.	180		\$0.00
<b>12.00</b>	<b>32 14 01</b>	<b>UNIT PAVING</b>				
12.01	1.6.3	Remove and Re-instate Brick Paver Driveway	SQ. M	80		\$0.00
<b>13.00</b>	<b>32 17 23</b>	<b>PAINTED PAVEMENT MARKINGS &amp; SIGNAGE</b>				
13.01	(1.5.2/1.5.3)	Line Painting & Thermoplastic Pvmt Markings	L.S.	1		\$0.00
13.02	(1.5.4)	Supply & Install or Adjust Traffic Signage (City to supply all new sign tabs)	L.S.	1		\$0.00
<b>14.00</b>	<b>32 91 21</b>	<b>TOPSOIL AND FINISH GRADING</b>				
14.01	(1.4.1)	Imported Topsoil - 150mm thick	C.M.	100		\$0.00
<b>15.00</b>	<b>32 92 23</b>	<b>SODDING</b>				
15.01	1.8.1	Sodding to Nursery Sod Specifications	SQ. M	450		\$0.00
<b>16.00</b>	<b>33 40 01</b>	<b>STORM SEWER</b>				
16.01	(1.6.5)	Catch Basin Lead - 150mm SDR28 PVC	L.M.	65		\$0.00
<b>17.00</b>	<b>33 44 01</b>	<b>MANHOLES &amp; CATCHBASINS</b>				
17.01	(1.5.2)	Install Top-inlet Catchbasin (MMCD S11)	EACH	7		\$0.00
17.02	(1.5.5)	Remove & Relocate Existing Catchbasin/Lawn Drain	EACH	4		\$0.00
17.03	(1.5.4)	Catchbasin Frame/Grate Replacement & Adjustments (Provisional)	EACH	6		\$0.00
17.04	(1.5.3.1)	Manhole Frame and Lid Replacement & Adjustments - (Provisional)	EACH	50		\$0.00
17.05	(1.5.3.2)	Water/Gas Valve Frame and Cover Replacement & Adjustments - (Provisional)	EACH	13		\$0.00
<b>18.00</b>	<b>34 41 13</b>	<b>TRAFFIC SIGNALS</b>				
18.01	1.9	Re-instate Traffic Detector Loops	EACH	4		\$0.00

**Total Tendered Price (exclude GST):** \_\_\_\_\_  
 (Transfer the amount to Form of Tender Summary Page 1)

**Name of Contractor:** \_\_\_\_\_