



Addendum No. 1

City of Coquitlam

Tender 77810

Walls Ave – Lebleu to Marmont Frontage Improvements

(Consists of 3 Pages)

Issue Date: March 15, 2021

Tenderers shall note the following changes:

Revisions

1. Refer to: FORM OF TENDER

REMOVE: Appendix 1
REPLACE with: **Revised Appendix 1 - Revision No. 1**

2. Refer to: PRECAST CONCRETE, Section 03 40 01S

Add Clause 1.4.7: "Payment for relocation of retaining wall to property line includes all work and incidentals, site preparation, 19mm Clear Crush Drain Rock backfill and capstone. Measurement of height for purpose of calculating areas for payment will be taken from the bottom of the installed wall to top of cap above the wall.

Payment for excavation and disposal of excavated material for the wall construction and removal of any existing retaining wall will be made under payment item, Common Excavation – offsite disposal, in the Schedule of Quantities and Price."

3. Refer to: PLANTING OF TREES, SHRUBS AND GROUND COVERS, Section 32 93 01S, Clause 1.9.1

DELETE: "root barrier" from the paragraph

Contractor Questions/Clarifications

Q1) Where will we be paid for the relocation of existing retaining wall at 1002 and 1013 Walls Ave?

A1) Use Pay Item 6.03. Refer to Form of Tender, Revised Appendix 1 - Revision No. 1.

Q2) What is the depth of the root barrier product to be installed?

A2) Install 400mm Deep Root barrier. Refer Revised Appendix 1 - Revision No. 1, Pay Item 18.03.

Q3) What is the length of the root barrier to be installed per tree?

A3) Install 3m on each side of the tree. Refer Revised Appendix 1 - Revision No. 1, Pay Item 18.03.

Q4) Will the root barrier be required on one side or both front and back of the tree?

A4) For trees behind sidewalk, install root barrier on sidewalk side. For trees in front of sidewalk, install root barriers behind curb and in front of sidewalk.

Q5) How do we get paid for the root barrier?

A5) Refer Revised Appendix 1 - Revision No. 1, Pay Item 18.03.

End of Addendum No. 1

Tenderers shall take into account the content of this Addendum in the preparation and submission of the Tender which will form part of the contract and should be acknowledged on the Tender form where indicated.

Upon submitting a Tender, Tenderers will be deemed to have received all addenda and considered the information for inclusion in the Tender submitted.

Issued by:

M. Pain
Purchasing Manager
Email: bid@coquitlam.ca

File #: 11-5330-20/77810/1 Doc #: 4010580.v1

Revised APPENDIX 1 - Revision No. 1
FORM OF TENDER**Contract 77810****Walls Ave - Lebleu to Marmont Frontage Improvements****SCHEDULE OF QUANTITIES AND PRICES**

(see paragraph 5.3.1 of the Instruction to Tenderers)

(All Tender and Contract Prices shall NOT include GST. GST will apply upon payment)**(Should there be any discrepancy in the information provided, the City's original file copy shall prevail)**

ITEM NO.	MMCD Ref. / (Supplementary Contract Specifications)	DESCRIPTION	UNIT	QTY	UNIT PRICE	EXTENDED AMOUNT
1.00	01 55 00	TRAFFIC CONTROL, VEHICLE ACCESS AND PARKING				
1.01	1.5.1	Traffic Control and Management			Incidental to Contract	
2.00	01 57 015	ENVIRONMENTAL PROTECTION				
2.01	(1.6.1)	ESC supply & installation, maintenance and removal			Incidental to Contract	
3.00	01 58 015	PROJECT IDENTIFICATION				
3.01	(1.3.1)	Construction Zone Information Signs	ea.	5		
4.00	03 30 205	CONCRETE WALKS, CURBS AND GUTTERS				
4.01	(1.4.3)	Concrete Curb & Gutter - Wide Base - MMCD C5	l.m	800		
4.02	(1.4.5)	Concrete Sidewalk & Walkway connectors & Wheelchair Letdown - 100mm thick - Broom Finished c/w 100mm Granular base; and as shown and described in the Contract Documents	sq.m	1,150		
4.03	(1.4.5)	Concrete Driveway Letdown, Sidewalk Crossing, and Driveways - COQ-C7 & COQ-C7B - 190mm thick c/w 100mm granular base; and as shown and described in the Contract Documents	sq.m	330		
4.04	(1.4.5)	Concrete Driveway Reinstatement, c/w 100mm granular base, Broom Finish	sq.m	70		
4.05	(1.4.5)	Concrete Driveway Reinstatement, c/w 100mm granular base, Stamped Concrete (Provisional)	sq.m	30		
4.06	(1.4.5)	Concrete Driveway Reinstatement, c/w 100mm granular base, Exposed Aggregate (Provisional)	sq.m	60		
4.07	(1.4.5)	Concrete Driveway Reinstatement, c/w 100mm granular base, Concrete Pavers (Provisional)	sq.m	15		
4.08	(1.4.10)	Tactile Strip - 24x48in - Access Tile, Yellow color - removable type	ea.	12		
5.00	03 30 535	CAST-IN-PLACE CONCRETE				
5.01	(1.5.3)	Concrete Stairs - Back of Sidewalk to Property Line (Provisional)	l.m	35		
6.00	03 40 015	PRECAST CONCRETE				
6.01	1.4.1	0.6m x 0.6m Paver - Front Boulevard - Concrete Connector Walkway	ea.	28		
6.02	(1.4.6)	Allan Block Retaining Wall (Includes clear crushed gravel, perf pipe, backfill, capstone) - segmental retaining wall (Provisional)	sq.m	20		
6.03	(1.4.7)	Existing wall relocation (Provisional)	sq.m	10		
7.00	26 56 015	ROADWAY LIGHTING				
7.01	1.9.2	Supply & installation of Roadway Lighting (ALL) Works including any removal, adjustments and disposal needed to complete the work and as shown on the Contract Drawing	l.s.	1		
7.02	(1.9.4)	Empty Ducts (c/w strings, caps on both ends); Telus & Shaw to supply their own rpvc ducts	l.s.	1		
8.00	31 05 17	AGGREGATES AND GRANULAR MATERIALS				
8.01	1.4.1	Imported Granular Fill, 75mm SGSB (Provisional)	tonne	300		
8.02	1.4.1	Clear Crushed, 19mm (Provisional)	tonne	30		
9.00	31 11 015	CLEARING AND GRUBBING				
9.01	(1.4.1)	Clearing & grubbing	l.s.	1		
9.02	1.4.2	Removal and disposal of Douglas Fir including stumps in front of 1061 Walls Ave (Provisional)	l.s.	1		
10.00	31 24 135	ROADWAY EXCAVATION, EMBANKMENT AND COMPACTION				
10.01	(1.8.4)	Removal and disposal of Existing Asphalt (all Depths), including asphalt curb, concrete, paver or sidewalks	sq.m	4,300		
10.02	(1.8.5)	Common Excavation including Off Site Disposal(includes retaining wall) (Provisional)	cu.m	1,500		
11.00	32 11 16.15	GRANULAR SUBBASE				
11.01	(1.4.3)	75mm Minus Granular Sub Base (Provisional)	tonne	750		
12.00	32 11 235	GRANULAR BASE				
12.01	(1.4.3)	25mm Minus Granular Base, variable thickness (Provisional)	tonne	1,200		
13.00	32 12 165	HOT-MIX ASPHALT CONCRETE PAVING				
13.01	(1.5.1)	Asphaltic Concrete Paving - Upper Course #1 (75mm, 1 lift)	tonne	610		
13.02	(1.5.3)	Asphaltic Concrete Paving - Driveways & sidewalks - Upper Course #2 (50mm, 1 lift), c/w 100mm Granular base	tonne	45		
13.03	1.5.4	Keyed in Extruded Asphalt Curb - 150mm high	l.m	30		
14.00	32 17 235	PAINTED PAVEMENT MARKINGS				
14.01	(1.5.3)	Supply & Installation Thermoplastic Pavement Markings (LAFRENTZ ROAD MARKINGS)	l.s.	1		
14.02	(1.5.4)	Remove and Reinstatement existing signage	ea.	4		

ITEM NO.	MMCD Ref. / (Supplementary Contract Specifications)	DESCRIPTION	UNIT	QTY	UNIT PRICE	EXTENDED AMOUNT
15.00	32 31 13	CHAIN LINK FENCES AND GATES				
15.01	1.5.3	Remove & Reinstall Existing Fence (Provisional)	l.m	20		
16.00	32 91 215	TOP SOIL AND FINISH GRADING				
16.01	(1.4.1)	Imported Topsoil - 150mm Thick for Sod	cu.m	150		
16.02	(1.4.1)	Growing Medium - Boulevard Tree Planting Trench - includes excavation, backfill, growing medium and as shown in Contract Drawings and described in Contract Documents(not paid where Boulevard Retention Trench is installed)	cu.m	610		
16.03	(1.4.1)	50mm Bark mulch (Provisional)	cu.m	4		
17.00	32 92 235	SODDING				
17.01	(1.8.1)	Sodding	sq.m	1,000		
18.00	32 93 015	PLANTING OF TREES, SHRUBS, AND GROUND COVERS				
18.01	(1.9.1)	Stewartia Pseudocamellia (Japanese Stewartia) 7cm Cal/B&B 2.0m STD.	ea.	17		
18.02	(1.9.1)	Styrax Japonicus Snowcone (Japanese Snowbell) 7cm Cal/B&B 2.0m STD.	ea.	15		
18.03	(1.9.3)	400mm Deep Root barrier, 3m each side of tree (Provisional)	l.m	310		
19.00	33 11 015	WATERWORKS				
19.01	(1.8.4)	19mm Service Connections - COQ-W2k as shown in Contract Drawings and as per Appendix B	ea.	3		
19.02	(1.8.4)	38mm Service Connections - COQ-W2d as shown in Contract Drawings and as per Appendix B	ea.	23		
19.03	(1.8.14)	Fire Hydrant Terminal City C71P c/w Storz	ea.	2		
20.00	33 30 015	SANITARY SEWERS				
20.01	(1.6.3)	Service Connections - 150mm SDR28 PVC c/w IC, as described in Contract Documents and as shown in Appendix B, COQ-S7A	ea.	9		
20.02	(1.6.3.1)	Service Connections Repair/Replacement (Provisional)	l.m	10		
20.03	(1.6.4)	Inspection Chambers - MMCD S9	ea.	4		
21.00	33 40 015	STORM SEWERS				
21.01	(1.6.3.1)	Storm Service Connection Repair/Replacement (Provisional)	l.m	25		
21.02	(1.6.4)	Inspection Chambers - MMCD S9 (Provisional)	ea.	13		
21.03	(1.6.5)	Catch Basin/Lawn Basin connection - 150mm SDR28 PVC	l.m	140		
21.04	(1.6.6)	French Drain (includes pipe, bedding, cleanout, tie-in to LB)	ea.	1		
21.05	(1.6.6)	Boulevard Retention Trench - COQ-SW3/SW4 (includes excavation, backfill materials, growing medium)	l.m	170		
21.06	(1.6.6)	Boulevard Retention Trench - Decant Piping (includes perf pipe, caps, cleanout, trench dam and tie in to C/B)	ea.	4		
21.07	(1.6.6)	Boulevard Retention Trench - Dispersal Piping (includes perf pipe, caps, cleanout, tie-in's to C/Bs / LBs)	ea.	4		
22.00	33 44 015	MANHOLES AND CATCHBASINS				
22.01	(1.5.2)	Top Inlet Catch Basin with 600mm Offsite Manhole - COQ-S11B (Provisional)	ea.	8		
22.02	(1.5.2)	Top Inlet Catch Basin MMCD S11 (Provisional)	ea.	8		
22.03	(1.5.2)	Side Inlet Catch Basin - COQ-S11A	ea.	2		
22.04	(1.5.2)	Lawn Basin - COQ-S12A Type 1, 300mm c/w bottom, as per Appendix B	ea.	8		
22.05	(1.5.3)	Manhole Frame and Lid Replacement & Adjustments	ea.	7		
22.06	1.5.4	Removal, Capping & Disposal of Catch Basins	ea.	8		

Total Tendered Price (exclude GST): \$ _____

(Transfer the amount to Form of Tender Summary Page 1)

Name of Contractor: _____