



Addendum No. 1

City of Coquitlam Tender 73580 Dawes Hill Road Rehabilitation

(Consists of 3 Pages)

Issue Date: April 23, 2021

Tenderers shall note the following changes:

Revisions

1. Refer to: FORM OF TENDER

REMOVE: Appendix 1
REPLACE with: **Revised Appendix 1 - Revision No. 1**

Contractor Questions/Clarifications

- Q1) Where will we be paid for the section between Finnigan Street and Mundy Street?
A1) Refer to Form of Tender, *Revised Appendix 1 - Revision No. 1.*
- Q2) How thick are the asphalt driveways?
A2) Contractor is to install 60mm thick asphalt.
- Q3) Under what item we get paid for LC#2 asphalt apron?
A3) Contractor is to use Lower Course #1 for asphalt apron and will be paid under Pay Item 10.02.
- Q4) What is the mix and thickness for the 1.2m asphalt sidewalk?
A4) Use Lower Course#1, 50mm thick.
- Q5) Can the closing date be extended?
A5) Tender Closing Date remains the same, April 27, 2021.

End of Addendum No. 1

Tenderers shall take into account the content of this Addendum in the preparation and submission of the Tender which will form part of the contract and should be acknowledged on the Tender form where indicated.

Upon submitting a Tender, Tenderers will be deemed to have received all addenda and considered the information for inclusion in the Tender submitted.

Issued by:

M. Pain
 Purchasing Manager
 Email: bid@coquitlam.ca

Revised APPENDIX 1 - Revision No. 1
FORM OF TENDER**Contract 73580-3**
Dawes Hill Road Rehabilitation**SCHEDULE OF QUANTITIES AND PRICES**

(see paragraph 5.3.1 of the Instruction to Tenderers)

(All Tender and Contract Prices shall NOT include GST. GST will apply upon payment)

(Should there be any discrepancy in the information provided, the City's original file copy shall prevail)

ITEM NO.	MMCD Ref. / (Supplementary Contract Specifications)	DESCRIPTION	UNIT	QTY	UNIT PRICE	EXTENDED AMOUNT
1.00	01 55 00	TRAFFIC CONTROL, VEHICLE ACCESS AND PARKING				
1.01	1.5.1	Traffic Control and Management			Incidental to Contract	
2.00	01 57 01S	ENVIRONMENTAL PROTECTION				
2.01	(1.6.1)	ESC supply & installation, maintenance and removal			Incidental to Contract	
3.00	01 58 01S	PROJECT IDENTIFICATION				
3.01	(1.3.1)	Construction Zone Information Signs	ea.	4		
Dawes Hill Road - Mundy Street to Cape Horn Avenue						
4.00	03 30 20S	CONCRETE WALKS, CURBS AND GUTTERS				
4.01	(1.4.3)	Concrete Curb & Gutter - Wide Base – MMCD C5	l.m	170		
4.02	(1.4.5)	Concrete Sidewalk, utility strip, wheelchair Letdown - 100mm thick – Broom Finished and as shown and described in the Contract Documents	sq.m	110		
4.03	(1.4.5)	Monolithic Concrete Sidewalk, utility strip, wheelchair Letdown - 100mm thick – Broom Finished and as shown and described in the Contract Documents	sq.m	85		
4.04	(1.4.5)	Concrete Driveway Letdown, Sidewalk Crossing - 190mm thick - COQ-C7 & COQ-C7B	sq.m	90		
4.05	(1.4.10)	Tactile Strip - 600x1500mm - Access Tile, Yellow color - removable type	ea.	5		
5.00	31 22 16S	RESHAPING GRANULAR ROADBED				
5.01	(1.4.1)	Reshaping	sq.m	7,700		
6.00	31 24 13S	ROADWAY EXCAVATION, EMBANKMENT AND COMPACTION				
6.01	(1.8.4)	Remove Existing Concrete -Sidewalk Panels, Utility Strips, Raised Median	sq.m	180		
6.02	(1.8.4)	Remove Existing Concrete Curb and Gutter	l.m	80		
6.03	(1.8.5)	Common Excavation Including Offsite Disposal (Provisional)	cu.m	300		
7.00	32 01 16.7	COLD MILLING				
7.01	(1.5.4)	Full Depth Milling (up to 150mm)	sq.m	7,700		
8.00	32 11 16.1S	GRANULAR SUBBASE				
8.01	(1.4.3)	75mm Minus Granular Sub Base (Provisional)	tonne	50		
9.00	32 11 23S	GRANULAR BASE				
9.01	(1.4.3)	25mm Minus Granular Base, variable thickness (Provisional)	tonne	550		
10.00	32 12 16S	HOT-MIX ASPHALT CONCRETE PAVING				
10.01	(1.5.1)	Machine Laid Hot Mix Asphalt (19mm MOT Class 1 Medium Mix with 80-100 Group A Asphalt Binder) - 50mm 1 lift	tonne	960		
10.02	(1.5.1)	Machine Laid Asphaltic Concrete Paving - Lower Course #1	tonne	970		
11.00	32 17 23S	PAINTED PAVEMENT MARKINGS				
11.01	(1.5.3)	Supply & Installation Thermoplastic Pavement Markings , including removal of existing pavement markings	l.s.	1		
11.02	(1.5.4)	Remove and Reinstall existing signage	l.s.	1		
12.00	32 91 21S	TOP SOIL AND FINISH GRADING				
12.01	(1.4.1)	Imported Topsoil - 150mm Thick for Sod	cu.m	25		
13.00	32 92 23S	SODDING				
13.01	(1.8.1)	Sodding	sq.m	150		
14.00	33 40 01S	STORM SEWERS				
14.01	(1.6.5)	Catch Basin lead connection - 150mm SDR28 PVC	l.m	40		
15.00	33 44 01S	MANHOLES AND CATCHBASINS				
15.01	(1.5.2)	Top Inlet Catch Basin - MMCD S11	ea.	1		
15.02	(1.5.2)	Side Inlet Catch Basin - COQ-S11A	ea.	3		
15.03	(1.5.3)	Manhole Frame and Lid Replacement & Adjustments (Provisional)	ea.	15		
15.04	(1.5.3)	Nelson Type Box Replacement & Adjustments (Provisional)	ea.	5		
15.05	1.5.4	Removal, Capping & Disposal of Catch Basins	ea.	3		
Dawes Hill Road - Finnigan Street to Mundy Street						
16.00	03 30 20S	CONCRETE WALKS, CURBS AND GUTTERS				
16.01	(1.4.3)	Concrete Curb & Gutter - Wide Base – MMCD C5	l.m	34		

ITEM NO.	MMCD Ref. / (Supplementary Contract Specifications)	DESCRIPTION	UNIT	QTY	UNIT PRICE	EXTENDED AMOUNT
16.02	(1.4.5)	Concrete Sidewalk, utility strip, wheelchair Letdown - 100mm thick – Broom Finished and as shown and described in the Contract Documents	sq.m	290		
16.03	(1.4.5)	Concrete Driveway Letdown, Sidewalk Crossing - 190mm thick - COQ-C7 & COQ-C7B	sq.m	65		
16.04	(1.4.10)	Tactile Strip - 600x1500mm - Access Tile, Yellow color - removable type	ea.	4		
17.00	31 11 01S	CLEARING AND GRUBBING				
17.01	(1.4.1)	Tree removal	ea.	1		
18.00	31 24 13S	ROADWAY EXCAVATION, EMBANKMENT, & COMPACTION				
18.01	(1.8.4)	Remove Existing Concrete -Sidewalk Panels, Utility Strips, Raised Median	sq.m	30		
18.02	(1.8.4)	Remove Existing Asphalt Driveways and Sidewalks (All Depths) (Sawcut, Removal, Offsite Disposal)	sq.m	100		
18.03	(1.8.4)	Remove Existing Concrete Curb and Gutter	l.m	20		
18.04	(1.8.5)	Common Excavation Including Offsite Disposal (Provisional)	cu.m	150		
19.00	32 11 23S	GRANULAR BASE				
19.01	(1.4.3)	25mm Minus Granular Base, variable thickness (Provisional)	tonne	85		
20.00	32 12 16S	HOT-MIX ASPHALT CONCRETE PAVING				
20.01	(1.5.1)	Machine Laid Asphaltic Concrete Paving - Lower Course #1	tonne	12		
21.00	32 17 23S	PAINTED PAVEMENT MARKINGS				
21.01	(1.5.3)	Supply & Installation Thermoplastic Pavement Markings , including removal of existing pavement markings	l.s.	1		
21.02	(1.5.4)	Remove and Reinstate existing signage	l.s.	1		
22.00	32 91 21S	TOP SOIL AND FINISH GRADING				
22.01	(1.4.1)	Imported Topsoil - 150mm Thick for Sod	cu.m	45		
23.00	32 92 23S	SODDING				
23.01	(1.8.1)	Sodding	sq.m	280		
24.00	33 44 01S	MANHOLES AND CATCHBASINS				
24.01	(1.5.2)	Catch Basin Frame Replacement & Adjustment	ea.	2		
24.02	(1.5.3)	Manhole Frame and Lid Replacement & Adjustments (Provisional)	ea.	5		

Total Tendered Price (exclude GST): \$ _____

(Transfer the amount to Form of Tender Summary Page 1)

Name of Contractor: _____