



Addendum No. 2

City of Coquitlam

Tender No. 77522

United Boulevard Multi-Use Pathway

Issue Date: May 5, 2022

(Consists of 4 Pages)

Tenderers shall note the following amendments to the **CONTRACT DOCUMENT** as follows:

1. Refer to: **FORM OF TENDER**

REMOVE:

FORM OF TENDER – APPENDIX 1 (FT. 5 to FT. 6)

REPLACE WITH:

FORM OF TENDER – **REVISED** - APPENDIX 1 – **REVISION 1** (REV 1 - FT. 5 to REV 1 - FT. 6)

Contractor Questions and Clarification(s)

- Q1) In response to question 3 on Addendum No. 1, please confirm that item 8.05 will be for asphalt stamping only and the asphalt supply and placement for this item will be paid under item 8.03 Asphaltic Concrete Paving - Machine Laid Upper Course #2 - 50mm MUP & Driveway.
- A1) That is correct, asphalt supply and placement will be paid under item 8.03.**
- Q2) General note 1 on the drawing states current Burnaby supplemental Specifications will be used. I would assume that this will be City of Coquitlam?
- A2) Correct.**
- Q3) Do you foresee any hydrovacating under tree driplines on this project? (General note 5)
- A3) No - trees are far enough from the work area that this would not be an issue.**
- Q4) Drawings note four (4) catch basins to be replaced, and the SOQ notes two (2) (item 14.01), please clarify.
- A4) Item 14.01 in the SOQ will be changed to four (4), see revised SOQ.**
- Q5) Item 5.02 - Removal and Disposal of Existing Concrete Curb and Gutter unit of measure is noted as sq m. Based off the takeoffs I believe this should be lm.
- A5) Item 5.02 unit of measure should be l.m. – see revised SOQ.**

End of Addendum No. 2

Tenderers shall take into account the content of this Addendum in the preparation and submission of the Tender which will form part of the contract and shall be acknowledged on the Tender Form, Item 1.

Upon submitting a Tender, Tenderers will be deemed to have received notice of all Addenda that are posted on the City's website and deemed to have considered the information for inclusion in the Tender submitted.

Issued by:

Mark Pain
Purchasing Manager
Email: bid@coquitlam.ca

REVISED - APPENDIX 1 - REVISION 1
FORM OF TENDER**Contract 77522****United Boulevard Multi-Use Pathway****SCHEDULE OF QUANTITIES AND PRICES**

(see paragraph 5.3.1 of the Instruction to Tenderers)

(All Tender and Contract Prices shall NOT include GST. GST will apply upon payment)**(Should there be any discrepancy in the information provided, the City's original file copy shall prevail)**

ITEM NO.	MMCD Ref. / (Supplementary Contract Specifications)	DESCRIPTION	UNIT	QTY	UNIT PRICE	EXTENDED AMOUNT
1.00	01 58 015	PROJECT IDENTIFICATION				
1.01	(1.3.1)	Construction Zone Information Signs	ea.	2		
2.00	03 30 205	CONCRETE WALKS, CURBS AND GUTTERS				
2.01	(1.4.3)	Concrete Curb & Gutter - Wide Base – MMCD C5	l.m	240		
2.02	(1.4.3)	Concrete Curb - 150mm High Extruded	l.m	8		
2.03	(1.4.5)	Concrete Sidewalk & Walkway Connectors & Wheelchair Letdown - 100mm thick – Broom Finished c/w 100mm Granular Base; and as shown and described in the Contract Documents	sq.m	20		
2.04	(1.4.10)	Tactile Strip - 24x60in - Access Tile, Yellow color - removable type	ea.	6		
3.00	26 56 015	ROADWAY LIGHTING				
3.01	1.9.2	Relocate Existing Street Lights and Base as per Contract Drawings	l.s.	1		
4.00	31 11 015	CLEARING AND GRUBBING				
4.01	(1.4.1)	Clearing & Grubbing	l.s.	1		
5.00	31 24 135	ROADWAY EXCAVATION, EMBANKMENT AND COMPACTION				
5.01	(1.8.4)	Removal and Disposal of Existing Concrete Sidewalk and Existing Asphalt (all Depths), including asphalt curb	sq.m	570		
5.02	(1.8.4)	Removal and Disposal of Existing Concrete Curb and Gutter	l.m.	240		
5.03	(1.8.4)	Railway Removal and Excavation Including Offsite Disposal	l.s.	1		
5.04	(1.8.5)	Common Excavation including Off Site Disposal	cu.m	580		
6.00	32 11 16.15	GRANULAR SUBBASE				
6.01	(1.4.3)	75mm Minus Granular Sub Base, variable thickness (Provisional)	tonne	410		
7.00	32 11 235	GRANULAR BASE				
7.01	(1.4.3)	19mm Minus Granular Base, variable thickness (Provisional)	tonne	340		
8.00	32 12 165	HOT-MIX ASPHALT CONCRETE PAVING				
8.01	(1.5.1)	Asphaltic Concrete Paving - Machine Laid Upper Course #1 - 50mm	tonne	30		
8.02	(1.5.1)	Asphaltic Concrete Paving - Machine Laid Lower Course #1 - 50mm	tonne	30		
8.03	(1.5.3)	Asphaltic Concrete Paving - Machine Laid Upper Course #2 - 50mm MUP & Driveway	tonne	130		
8.04	(1.5.3)	Asphaltic Concrete Paving - Machine Laid Lower Course #2 - 50mm Driveway	tonne	25		
8.05	(1.5.3)	Asphalt Stamping - Concrete Grey with Offset Brick Pattern	sq.m.	95		
8.06	1.5.4	Asphalt Extruded Curb - 150mm High	tonne	4		
9.00	32 17 235	PAINTED PAVEMENT MARKINGS				
9.01	(1.5.3)	Supply & Installation Thermoplastic Pavement Markings	l.s.	1		
9.02	(1.5.3)	Supply & Installation of "Vancouver Green" MMA Paint	l.s.	1		
9.03	(1.5.4)	Remove and Reinstall Existing Signage, Eradicate Existing Markings as per Contract Drawings	ea.	7		
9.04	(1.5.4)	Install New Signage and Sign Structure (City Supplied Signs)	ea.	8		
10.00	32 31 13	CHAIN LINK FENCES AND GATES				
10.01	(1.5.5)	MOTI 2891-2 Railing	l.m.	65		
10.02	(1.5.4)	Removable Steel Bollards - Model R-901 c/w base receiver. Refer to Appendix B.	ea.	4		
11.00	32 91 215	TOP SOIL AND FINISH GRADING				
11.01	(1.4.1)	Imported Topsoil - 150mm Thick	cu.m	45		
12.00	32 92 195	HYDRAULIC SEEDING				
12.01	1.8.2	Hydraulic Seeding	sq.m	300		

ITEM NO.	MMCD Ref. / (Supplementary Contract Specifications)	DESCRIPTION	UNIT	QTY	UNIT PRICE	EXTENDED AMOUNT
13.00	33 40 015	STORM SEWERS				
13.01	(1.6.5)	Catch Basin/Lawn Basin connection - 150mm SDR28 PVC (including sanded stubs)	l.m	16		
14.00	33 44 015	MANHOLES AND CATCHBASINS				
14.01	(1.5.2)	Top Inlet Catch Basin MMCD S11	ea.	4		
14.02	1.5.4	Removal, Capping & Disposal of Catch Basins	ea.	1		

Total Tendered Price (exclude GST): \$ _____
(Transfer the amount to Form of Tender Summary Page 1)

Name of Contractor: _____